

Chains

by the surveyor general. At this point I set
a boulder stone 15x8x6 ins 12 ins in the ground for
closing cor. of secs. 22 and 27, marked C.C. on
E. face, with 4 notches on N. and 2 notches on
S. edges, and raised a mound of stone 2 ft base 11
ft high N. of cor. Pits impracticable.
I re-established the old cor. of secs. 21-22-27 & 28
already described, in its original place, as the
cor. of secs. 24 and 28, by raising a mound of
stone 2 ft base 11 ft high N. of the original cor.
Pits impracticable.

Land mountainous and broken
Soil stony; 4th rate,
No timber.
Mountainous land 73.73 chs. ⑦

From the cor. of Secs. 22-23-26 and 27,

I run
S 02° 09' W, on a true live bit, Secs 26 and 27.

Descending over stony ground,
Bottom of ravine 200 ft below cor. course S 40° E. Begin to desc
Top of ridge 100 ft above bottom of ravine course S 35° E, N 35° W
Bottom of steep descent, at N. side of Harris Canon, 300 ft
below ridge, course S 50° W, N 50° E
Wood road bears S 30° W, N 50° E
Creek bed (dry) course S 50° W, N 50° E

40.15
42.40
30.00
32.50
33.50
34.35
36.50
39.05
39.73
40.00

Foot of ascent bears S 47° W, N 47° E,
Top of spur sloping W. Begin descent,
Foot of descent into S. Fork of Harris Canon, bears N 55° W.
Creek bed (dry) course N 55° W.

Set boulder stone 14x6x6 ins 9 ins in the ground for
1/4 sec. cor. marked 1/4 on N. face, and raised a mound
of stone 2 ft base 11 ft high W. of cor. Pits impracticable.

Wood road bears N 78° W, S 78° E,

Begin ascent of S. side of canon
Top of steep ascent, 300 ft above bottom of canon.

Slide over broken ground sloping N.

Begin descent, at head of Harris Canon, facing S.
I intersect the sec. line 3.68 chs N. of the old
cor. to Secs. 26-27-34 and 35, which is a stone
firmly set marked and witnessed as described
by the surveyor general; and re-established by me
in its original place as the N.E. cor. of sec 34,
heretofore described.

at this point
I set a boulder stone 14x10x8 ins 9 ins in the ground
for closing cor. of Secs. 26 & 27, marked C.C. on
N. face, with 2 notches on E. & 4 notches on W.
edges, and raised a mound of stone 2 ft base 11
ft high N. of cor. Pits impracticable.

Land mountainous & broken,
Soil stony; 4th rate,
No timber.
Mountainous land 78.32 chs

⑧

August 15-1895.