

Chains.

- 12.90 N 0°-10' E, bet. secs. 13 and 14
Ascending over stony ground sloping S.E.
Top of ridge 150 ft above the Sec. cr. course S 10° W. 97 ft
Being boundary line between Summit County on S. and
Madison County on the N. Begin ascent,
24.75 Enter aspen and maple brush 8° W,
26.75 Leave aspen and maple brush 8° W,
34.75 road road, bearing 145° E. & S 45° W, in bottom of
Wood Run Cañon. Begin ascent,
40.00 Set quartzite boulder stone 16x6x6 ins 9 ins in the
ground for 1/4 sec. cr. marked 1/4 on W. face, and marked
a mound of stone 2 ft base 1 1/2 ft high N. of cor.
Pits impracticable
52.75 Top of ridge 200 ft above 1/4 sec. cr. course 8° W, Begin de-
scend oak and maple brush
68.00 Bottom of ravine 250 ft below top of ridge, bears N 70° W,
Leaves brush, begin ascent,
73.00 Top of spur alpine W. Begin descent
74.00 Bottom of ravine course S 45° W & N, 80° E
80.00 Set quartzite boulder stone 16x12x10 ins 11 ins in the
ground for cor. of sec. 11-12-13 and 14, marked with
1 notch on E. and 4 notches on S, edges just raised &
mound of stone 2 ft base 1 1/2 ft high N. of cor.
Pits impracticable
Land mountainous and broken
Soil alluvial and stony, 1st & 4th rate.
Timber, scattering aspen,
Mountainous land 80.00 chs. (11) ✓

- 40.00 N 89°-59' E. on a random line bet secs. 12 and 13.
79.58 Set temp. 1/4 sec. cr.
Intersect E. bdy of sp. 3 lks N. of cor. of Secs. 7-12-13 and 18,
which is a boulder stone 8x60x5 ins and above ground, furnish
all marked and witnessed as described by the surveyor
general.
Thence, I run,
N. on a true line bet. secs 12 and 13,
through thick oak brush and over ground sloping N.
Leave brush, begin descent over ground sloping N. W.
3.00 Bottom of canon 200 ft below the sec. cr. course N. 25° W,
25.00 Begin ascent, through oak and willow brush,
39.79 Set quartzite boulder stone 18x7x7 ins 12 ins in the ground
for 1/4 sec. cr. marked 1/4 on N. face, edge pits 18x18x9 ins
E & W of stone 3 ft dist.; just raised a mound of
earth 3 1/2 ft base, 1 1/2 ft high N. of cor.
40.80 Top of ascent, 200 ft above bottom of canon, Leave brush, begin
descent over ground sloping N. W.
53.00 Bottom of ravine 150 ft below the 1/4 sec. cr. bears N 45° E,
and contains scattering aspen, begin ascent,
63.00 Top of ridge 100 ft above bottom of ravine bears N 30° E
& S 30° W, begin descent, at head of ravine bears
N.
79.58 The cor. of secs. 11-12-13 and 14,
Land mountainous and broken,
Soil alluvial, 1st rate,
Timber, scattering aspen,
Mountainous land 79.58 chs. (12) ✓