

chains.
8.75
17.75

N 0°-10° E. bet. secs, 11 and 12.
Ascending over stony ground
top of ridge 250 ft above the sec. cor. bears N 60° W. 7 S. 60° E.
Slope descent, over broken ground sloping N. E.
Spring sloping N. E. Begin descent, into West
fork of Black Hawk Canon.

40.00
49.50
70.00

Set quartzite boulder stone 18 X 8 X 6 ins 12 ins in the
ground for 1/4 sec. cor. marked "from N. face", and raised
a mound of stone 2 ft base, 1 1/2 ft high W. of cor.
Pits impracticable.
Bottom of W. fork of Black Hawk Canon. 400 ft below
the top ridge, bearing N 50° E. Very small
springs rise and flow N. E. Begin ascent, of West
side of canon.

80.00

Top of bridge 300 ft above bottom of canon, bears N 10° E,
& S 15° W. Descent along W. slope of ridge.
Set quartzite boulder stone. 14 X 8 X 6 ins in the ground
for cor. of secs. 1-2-11 and 12, marked with 1 notch on E. side
and 5 notches on S. edges, and raised a mound of stone
2 ft base, 1 1/2 ft high W. of cor. Pits impracticable.

Land mountains and broken
Soil stony; A² rate.
No timber.
Mountainous land 80.00 chs.

(13) ✓

40.00
79.50

E. on a random line bet. secs. 1 and 12.
Set trap 1/2 sec. cor.
Intersect E. side of cor. at the cor. of secs. 1-6-7-9 12, which
is a white sand stone 6 X 6 X 6 ins above ground, firmly
set, marked and witnessed as described by the surveyor
Thence I run

3.60
8.00

W. on a true line bet. Secs. 1 and 12.
ascending over broken ground
Top of ascending trail N 4° S. Thence over broken ground sloping
N. S. side of Cedar Canon,
Timber oak brush, N & S.

12.30
28.00
39.90

Begin descent into Black Hawk Canon, bears N 45° W.
Set gray sand stone 15 X 10 X 5 ins 10 ins in the ground
for 1/4 sec. cor. marked "from N. face" and raised a mound
of stone 1 1/2 ft high W. of cor. Pits impracticable.
Top of descent in Black Hawk Canon 400 ft below
the beginning of descent, course, N 45° W. Thence over
level land

50.00
50.90
55.50
56.10
75.00

Wood road W. and S 45° E
Creek bed 2 ft deep 1 1/2 ft wide (dry) drains North
Begin very steep ascent W. side of Black Canon.
Top of ridge 800 feet above bottom of Canon, bears
N 150° E. & S. 15° W. Begin descent, along W. slope
of ridge
at the cor. of secs. 1-2-11 & 12.

79.80

Land mountains & broken
Soil alluvial and sandy; 1st and 3rd rate,
Timber scattering
mountainous land 79.80 chs.

(14) ✓