

6.00
16.00
25.52
30.50
31.30

on their line
N 0° 10' E. lat. Secs 1- and 2
Descending over broken ground, sloping N.W.
Foot of descent, since along ground nearly level,
Top of steep descent, sloping N.
entirely scattering pine, E & W
Leaves scattering pine, E & W.
Foot of descent 400 ft below beginning descent, at S side of
Edward Cannon, Corvair W. (Eastern mostly bottom land, occupied
and claimed by Gen. Shackera, and Joseph Condit. The
line running N. & S, lat. this claim, Shackera, & Condit, and
John Hopkins claim, bears E. 30° dist west.

35.86
37.35
38.62
40.00
44.25
63.70

Creek 2 feet deep, 3 ft wide, pure cold water, course N 80° W, leaves
marshy bottom land, center meadow.
Leaves Shackera and Condit's meadow and claim, N. end of top
running N & S, lat. Shackera & Condit's claim and John
Hopkins claim, bears E. 30° dist west
Wood road, bears E & W. Begin ascent
Set quartzite boulder stone 16 x 8 x 7, ins 10 ins in the ground
for 1/4 sec. cor. marked 1/4 on W. gale, and raised a mound
of stones 2 1/2 ft high N. of cor, pits impracticable
Foot of steep descent, N. side of Canon D
Top of ridge 400 ft above bottom of canon, bears S 40° W
Descend along ground sloping N.W.

79.60

Intrusect N. side of Sp. at the standard cor of Secs. 35 and 36
which is a gray sand stone 7 1/2 ft 6 in above ground formerly
set unmarked, and witnessed as described by the survey
generals, which I mark C.C. on S. gale for closing
feet of sec. 1 and 2, and raise a mound of stone
2 ft 7 bars, 1 1/2 ft high S. of cor, pits impracticable.
Land mountainous and broken,
Soil alluvial and rocky, 1st and 4th pate.
Timber, a few scattering pine,
Mountainous land 73.55 chs.

(15) ✓

August 17-1895,

By my watch

August 20th 1895, at 9^h 26^m P.M. limit, or at 9^h 52 P.M.
Mountain standard rail road time I observe Polaris at
Eastern elongation in accordance with Manual of Instruct
at the Cor. of Secs 22-23-26 and 27 and mark a
point in the line this determined by a tack driven in
a wooden plug set in the ground 5 chs N. of my station.

August 20-1895

August 21st at 8. A.M. mountain standard R.R. time
2 days of the azimuth of Polaris 1240' to the west and
mark of the true meridian, this determined by a tack
driven in a wooden plug set in the ground West of the
point established last night.

6.50
33.50

channel & dam
N 0° 9' E lat. Secs 22 and 23
ascend over stony ground sloping S.W.
Top of ridge 775 ft above sec. 1 cor, bearing S 10° 34' 10" W.
Continue ascent along E. slope of ridge, over broken
top of ridge 250 ft above sec. cor, bearing S 45° W
and N 15° E. Round the boundary line lat. Summit Co. on the
S, and Morgan County on the North. Begin descent,