

Chanis

47. on N.W. and 48. on S.W. faces
marked with 3 notches on the E. and
S. edges, and raised a mound of stone
2 ft base, 1 1/2 ft high N. of cor. of pits imprac-

thence I run
389 ± 53' E on a true line lat. Decs. 15 and 22.
Ascending over gravel sloping N.
Bottom of ravine 50 ft deep 5 chs. wide lower N.
Bottom of ravine 50 ft deep 3 chs. wide lower N.
Set boulder stone 16 x 8 x 6 ins 11 ins in the
for 1/4 sec. or marked 1/4 on N. face, and raised
by mound of stone 2 ft base 1 1/2 ft high N. of
Pits impracticable. Begin steep ascent.
Top of ridge 250 ft above the 1st sec. cor. covers
31. 3 Begin descent.
Bottom of ravine 50 ft below ridge covers 8.
Small spring base 31 about 10 chs dist. flows N.
Begin steep ascent over rocky ground sloping S.
The cor. of seas 14-15-22 and 23.

25.00
33.25
33.76

65.75

68.25

73.76

Land mountainous and broken,
Soil rocky and loam; 3rd and 4th rate.
No timber.
Mountainous land 73.76 chs.

(18) V

N. 0° 09' E lat seas 14 and 15.
Descending over rough stony ground sloping N.E.
Bottom of N. fork of Wolf Den Canyon, 300 feet
1/4 sec. cor. covers N 80° W.
Wood road drain N 80° W. & S 80° E.
Creek bed (dry) covers N.W.
Begin ascent over rocky ground.
Top of spur sloping N. Begin descent.
Set boulder stone 14 x 8 x 6 ins 9 ins in
the ground for 1/4 sec. cor. marked 1/4 on N. face
and raised by mound of stone 2 ft base 1 1/2 ft
N. of cor. Pits impracticable.

27.90
28.03
28.40
29.70
33.30
40.00

42.70

62.00

79.75

80.00

Bottom of N. fork of Wolf Den Canyon, covers S 45° W.
Begin descent over rocky ground, sloping S.E.
Top of ridge 275 ft above bottom of canyon, base 350
& 170 50° E. Begin descent over broken ground
sloping N. and N.W.
Cobblestone ledge 20 ft high base N 10
& S 10° E. at head of ravine, draining S.W.
Begin steep ascent.
Set gray sandstone 16 x 10 x 5 in 10 ins in the
for cor. of seas 10-11-14 and 15. marked with
2 notches on E. and 4 notches on the S. edges
and raised a mound of stone 2 ft base 1 1/2 ft
N. of cor. Pits impracticable.

Land mountainous and broken,
Soil stony; 4th rate,
No timber.
Mountainous land 80.00 chs.

(19) V