

S89°-59'E on a random line bet. secs. 11 and 14.

40.00
80.04

Set traps $\frac{1}{4}$ sec. cor.
Intersect N9 S. line 3 lvs S. of the cor of secs
11-12-13 and 14.
Thence $\frac{1}{2}$ run,
W. on a true line bet. secs. 11-14,
Descend over stony ground,

75
7.50
12.90
17.40
21.60
25.40
33.00
40.00

Bottom of ravine, course S. Begin ascent,
Top of ridge 150 ft above 360 cor. course S. Begin descent,
Bottom of ravine, 100 ft below ridge, course S. Begin ascent,
Top of ridge 125 ft above ravine, course S. Begin descent,
Bottom of ravine, 125 ft below ridge, course S. Begin ascent,
Top of ridge 150 ft above ravine, course S. Begin descent,
Bottom of ravine, 200 ft below ridge, course S. Begin ascent,
Set gray sand stone 14 X 8 X 6 ins in the ground for
 $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face, and raised a mound
of stone 2 ft base 1 1/2 ft high N. of cor. Pile impracticable.

40.90
45.50
54.40
66.60
79.50
80.04

Top of ridge 250 ft above bottom of ravine, course S.
Thence over ground sloping S.
Begin steep descent, over ground sloping W.
Bottom of ravine 300 ft. below ridge, course S. Begin ascent,
Top of ridge 400 ft above ravine, course S10°W, $\frac{1}{2}$ N10°E, descent,
Bottom of ravine, 375 ft below ridge, course S10°W,
The cor. of secs. 10-11, 14 and 15.

Land mountainous and broken
Soil stony. 4th rate.
Timber a few scattering aspen S. of the line
Mountainous land. 80.00 chs. D

(20) ✓

13.60
18.80
34.00
38.00
40.00
41.70
57.60
66.70
76.00
80.00

N209° E. bet. secs 10 and 11,
ascending over steep rocky ground sloping S.
Top of ridge 500 ft above cor. course S. $\frac{1}{2}$ W.
Bottom of Woodbury and Brewer Canons, Begin
steep descent into Brewer Canon.
Enter scattering dead aspen, course S. $\frac{1}{2}$ W.
Bottom of Brewer Canon 600 ft below ridge, course S
N70°W. Grow dead aspen, Begin ascent,
Top of aspen sloping W. Begin descent,
Set gray sand stone 16 X 8 X 4 ins in the ground
for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face, and raised a
mound of stone 2 ft base, 1 1/2 ft high N. of cor.
Pile impracticable.
Branch $\frac{1}{4}$ inch deep 3 ins wide, course S. S45°W,
A small spring, course N45°E 1.0 chs. dist. the corner
of this branch. Bottom of St. Fork of Brewer Canon
Begin ascent, over ground sloping S. 0.11
Top of ridge 200 ft above bottom of Canon, course N40°E
and S10°E. Thence over ground sloping N. W.
Bottom of ravine 20 ft below ridge above S40°W,
Begin descent ascent,
Top of steep ascent, thence over ground sloping W.
Set boulder stone 18 X 8 X 6 ins in the ground
for cor. of secs. 2-3-10 and 11, marked with 2 notches
on the E. and 5 notches on the S. edge, and raised
a mound of stone 2 ft base, 1 1/2 ft high N. of cor.
Pile impracticable.

Land mountainous and broken.
Soil stony. 4th rate.
Timber a few scattering dead aspen.
Mountainous land 80.00 chs.

(21) ✓