

Chains
40.00
80.02

From a random line bet secs. 2 and 11.
Set comp. 1/4 sec. cor.
Intersect N+S. line 2 lks S. of cor. of Secs. 1-2-11-12
Thence I run
S89°59' W. on a true line bet. Secs. 2 and 11.
Descending over ground sloping N.W.
Bottom of ravine, 200 ft below the sec. cor. course N10° W. Begin ascent
Top of spur sloping N. Begin descent.
Bottom of canon, 300 ft below sec. cor. course 1 North.
Parade 1/2 inch deep, 3 in wide, drains N. and thence into
Cedar Canon. Begin ascent.
Top of spur, 200 ft above, course S, continue ascent
along ground sloping S.E.
Head of ravine, course S.E.
Set quartzite boulder stone 15 x 6 x 5 ins 1/2 in in the
ground 1/4 to 1/2 sec. cor. marked 1/2 on N. face, and raised
a mound of stone 2 ft base 1 1/2 ft high. N. of cor.
File impracticable.
Top of rocky ridge 500 ft above bottom of canon, course
N150° E + S115° W. Begin steep descent
Bottom of ravine 175 ft below ridge, course N 40° W.
Begin ascent.
Top of spur, 50 ft above ravine, slope N. Begin descent
Bottom of ravine 50 ft below spur, course N10° E. Begin
ascent.
Top of ridge 200 ft above ^{bottom of} ravine, course N 40° W. + S 40° E.
Begin descent.
The cor. of Secs. 2-3-10 and 11, 75 ft below, top of ridge,

Land mountainous and broken
Soil, boulders and loam; 3rd and 4th rate
Timber a few scattering aspens. S. of the line.
Mountainous land. 80.02 club.

(22) ✓

40.00
73.86

N 89°53' W on a random line bet. Secs. 10 and 15.
Set comp. 1/4 sec. cor. 4 lks S. of the cor. of Secs. 9-10-15, 1
Intersect N+S. line 2 lks S. of the cor. of Secs. 9-10-15, 1
which is a gray sandstone 15 x 8 x 3 ins above ground
firmly set, marked and witnessed as described by
the Surveyor general.

Thence I run
S89°51' E. on a true line bet. Secs. 10 and 15.
Over clay and broken ground; descend.
Bottom of ravine 10 ft below the cor. course S 40° W.
Begin ascent.
Top of ascent, 75 ft above ravine, course N40° E + S40° W
Begin descent, over ground nearly level.
Begin steep descent, 340° W. N. 40° E.
Bottom of ravine, 75 ft deep, course S 35° W. Begin ascent
Top of ascent, about 90 ft above ravine, course S 35° W.
Thence ascend over broken ground,
Begin descent.
Bottom of ravine about 75 ft deep, course S 45° W.
Begin descent, over ground sloping S.W.
Set quartzite boulder 20 x 6 x 6 ins 15 in in the ground
for 1/4 sec. cor. marked 1/2 on N. face, and raised a
mound of stone 2 ft base, 1 1/2 ft high. N. of cor.
File impracticable.
Top of ridge 30 ft above 1/4 sec. cor. course S 45° W. Begin
descent.
Bottom of ravine about 50 ft below beginning of descent, course
S.W. Begin ascent.
Top of ridge 75 ft above bottom of ravine, course S.W.
Continue ascent over ground sloping S.

76
3.00
9.30
7.50
11.30
26.52
29.40
33.80
37.50
41.30
44.30