

Chains

3.41  
4.75  
73.86

Bottom of ravine, course S 20° W, Begin steep ascent,  
Top of ridge 100 ft. above bottom of ravine, course S,  
Continue ascent over rocky ground,  
The cor. of secs. 10-11-14 and 15, about 100 ft above  
top of ridge  
Lard mountainous and broken  
Soil stony, 1/2 rate,  
No timber.  
Mountainous land 73.86 chs.

(23) ✓

August 21-1895.

Sept. 1st 1895 at 8-39<sup>m</sup> P.M. 2 mt. or at 9<sup>m</sup> 5<sup>m</sup> P.M.  
by my watch which is mountain standard rail  
road time, I observe Polaris at eastern elongation  
in accordance with Manual of Instructions, at the  
cor. of secs. 2, 3, 10 and 11, and make a point in  
the line thus determined by a tack driven in a  
wooden plug set in the ground 40 ch N. of my  
station; a ridge obstructs the view at S. chs, North,  
Sept 1st 1895.

Sept 2nd 1895, at 8, A.M. I lay off the azimuth of  
Polaris, 1° 40' to the west, and make the true S.  
meridian thus determined, by a tack driven in  
a wooden plug set in the ground West of the  
point established last night.

Thence I run

4.50  
15.15  
18.20

N 0° 09' E, bet secs. 2 and 3,  
Ascend ing over stony ground,  
Top of ridge 75 ft above the sec. cor. bearing E 7 N, Begin  
descent.

40.00

Enter scattering ashew Leas E 7 W.  
Bottom of canon 60 ft below ridge; course N 40° E, abt  
10. chs thence N. Leas above, bearing S. 73 40° W.  
Descend along ground sloping E. 4 N. E. on W. side of  
Canon.

58.22

Set gray sandstone 14 X 10 X 7 ins 9 ins in the ground  
for 1/4 sec. cor. marked 1/4 on W. face, and raised  
a mound of stone 2 ft base 1 1/2 ft high N. of cor,  
Pile impracticable.

61.70  
66.54

First of descent in bottom of Cedar Canon, <sup>abt 500 ft</sup>  
below the ridge Leas N 75° W, and S 65° E, to Hopkins claim  
Set quartzite boulder stone 22 X 11 X 8 and 17 ins in the  
ground for wander cor. of grad. secs. 2 & 3,  
marked M.C. on N. face, with 2 grooves on  
E. face; and raised a mound of stone  
2 ft base 1 1/2 ft high S. of cor. Pile impracticable.

66.64

Enter Hopkins alfalfa field, to S E. 7 N. W.  
Cedar Creek 3 ft wide 1 ft deep, course W.  
Leas John Hopkins alfalfa field and claim.

66.64

Set quartzite boulder stone 19 X 11 X 6 ins 14 ins in the  
ground for wander cor. of grad. secs. 2 and 3,  
marked M.C. on S. face, with 2 grooves on E. face  
and raised a mound of stone 2 ft base 1 1/2 ft high  
N. of cor. Pile impracticable.  
Wood road Leas N 64° W, and S 64° E.