

chains

7.50
9.00
16.70
36.03
36.66
37.12
40.00
41.66
42.00
42.00

N 2° 09' E, but sec's 3 and 4,
 Descending over rough stony ground, sloping N.
 Bottom of Little Forester Canyon, 200 feet below the sec,
 cor. course N 80° W, Enter cottonwood grove, E & W,
 Leave cottonwood grove base E & W. Mean ascent,
 top of ascent 200 ft above bottom of Canyon. Present
 descent over ground sloping N, into Lost Creek Canyon.
 Wire fence bears N 56° E & S 32° W, at Lost Creek bottom
 Set quartzite boulder stone 14x6x6 ins. 9 ins in the
 ground for witness cor. to 1/4 sec, cor. marked N.C. 1/4
 on N. face. From which a cottonwood tree set up
 diam bears N 5° E 47 Chesdick marked N.C. 1/4
 S. Cottonwood tree 14 in diam bears N 6° W, 41 Chesdick
 marked N.C. 1/4 S. PT
 Foot of descent, bears N 40° E & S 40° W, Enter Lost Creek
 bottom. Thence over gravelly bottom subject to
 overflow
 Set quartzite boulder stone 14x6x6 ins in the
 ground for 1/4 sec, cor. marked 1/4 in N. face and
 raised a mound of stone 2 ft base 1 1/2 ft high
 E. of cor. Pits impracticable.
 S. Side of Lost Creek 1 ft deep, course S 10° W by
 leads over boulder bottom. Subsequent definite banks
 rapid descent.
 N. Side of creek Thence over gravel and boulders
 through scattering cottonwood timber.

56.00
56.68
56.90
71.60
72.24
79.59

From rocky bottom land. Thence over gravelly loam
 Enter John Hopkins old land claim.
 Set quartzite boulder stone 18x6x6 ins 12 ins in the
 ground for witness cor. of frac sec, E, marked M.C.
 on N. face, with 3 points on E. face, and raised a
 mound of stone 2 ft base 1 1/2 ft high E. of cor.
 Pits impracticable.
 Irrigation ditch 3 ft wide 2 ft deep, course S 70° W
 Enter John Hopkins old land claim, bears S 70° W, & N. 70° E, and
 over level land
 Wire fence bears N 35° E, & S 35° W, Leave John
 Hopkins old land claim.
 Set a quartzite boulder stone 14x8x6 ins 9 ins in
 the ground for witness cor. of frac sec, 3 marked
 M.C. on S. face with 3 points on E. face and
 raised a mound of stone 2 ft base 1 1/2 ft high M.
 of cor. Pits impracticable.
 Wagon road, from Floyd up Lost Creek Canyon
 1/2 m. aspen, over rocky ground.
 Intersect N. side of sp. 1/2 E of the standard cor.
 of sec. 33 & 34, heretofore described, which
 I mark C.C. on S. face for closing cor. of sec's
 3 and 4, and raised a mound of stone 2 ft base
 1 1/2 ft high S. of cor. Pits impracticable.

land mountainous and level
 Soil stony, and loam; 3rd & 4th hole
 timber scattering cottonwood, on creek bottom.
 Mountainous land 44, 47 chs.

(76) ✓