

Chains.

- 5.02-09' W. bat sees. Grand 10.  
 Ascending over rocky and broken ground  
 Top of spur 150 ft above base of main W. begin descent  
 Bottom of Forest Canyon, 100 ft below top of spur  
 corner of N. small spur <sup>over</sup> about 10 chs dist. Does not go  
 Begin steep ascent  
 9.84 Set gray sandstone 18x12x6 ins 12 ins in the ground  
 27.00 for the sec. cov. marked 1/4 on N. face and raised a mound  
 40.00 of stone 2 ft base 1 1/2 ft high 1 1/2 ft cor. Pits impracticable  
 43.52 Top of spur about 500 ft above bottom of Forest Can  
 51.00 Grist W. thence along ground slope W.  
 Top of ridge, 10 ft above top of spur, bearing N 40° W.  
 54.00 Descend  
 Bottom of ravine 50 ft below ridge. Course N 40° W,  
 ascend  
 56.30 Top of ridge 40 ft above bottom ravine bears N 40° W  
 & S 60° E. on N. side of Wolf Den Can. Descend  
 abruptly.  
 79.80 Inverse E. and N. line 6.14 chs N. of the cor. of  
 sees. 9-10-15 and 16, here they separated.  
 Set quartzite boulder stone 20x10x8 ins 15 ins in the  
 ground for clearing cov. of sees. 9 and 10 marked C.C. on  
 N. face with 3 notches in E. & 3 notches on W.  
 edges, and raised a mound of stone 2 ft base 1 1/2 ft  
 high N. of cor. Pits impracticable.  
 I re-establish the old cor. of sees. 9-10-15 & 16,  
 in its original position, as the cor. of sees. 15 and 16  
 by raising a mound of stone 2 ft base 1 1/2 ft high  
 S. of the old cor. Pits impracticable.  
 Sand-mountainous and broken,  
 Soil rocky. 4<sup>th</sup> rate,  
 No timber.  
 Mountainous land 79.80 chs.

(27) ✓

- N. on a true line bet sees 4 and 9.  
 Descending over rocky ground sloping W.  
 23.25 Foot of descent in Lost Creek Bottom 400 ft below  
 30.00 top of Forest 335° W. & N. 35° E. Thence lower level  
 26.75 gravelly creek bed, through scattering cotton wood brush  
 E. edge of Lost Creek, 1/2 ch dist. 53 chs wide, covered  
 W. Flood over banks and gravel bottom, grate over  
 bare water. No well defined banks  
 27.27 W. side creek. Sand over sand and gravelly sand  
 35.25 Wagon road bears N 39° E. 339° W. from Crooked  
 35.41 Lost Creek Canyon. 332° W. & N 39° E. Enter Jacob Mole  
 old land claim.  
 Set quartzite boulder stone 16x6x6 ins 11 ins in the  
 ground for mound cov. of gravel. Sees 4 and 9 marked  
 W. E. and N. face with 5 notches on E. face, and raised  
 a mound of stone 2 ft base 1 1/2 ft high E. of cor. Pits  
 impracticable.  
 35.75 Irrigating ditch 3 ft wide 1 1/2 ft deep. course S 40° W,  
 enter alfalfa field.  
 40.00 Set quartzite boulder stone 14x8x6 ins 9 ins in the  
 ground for the sec. cov. marked 1/4 on N. face. Aug pits  
 18x18x12 ins E. & W. of stone 3 notches and raised  
 a mound of earth 3 1/2 ft base 1 1/2 ft high N. of cor.  
 49.09 Irrigating ditch, 3 ft wide 1 ft deep. course S 45° E.  
 52.00 Gravelly alfalfa field. Thence over stony ground,  
 wire fence, bearing N 26° E. & S 23° W. N. side of Jacob Mole