

62.00 Top of spur 125 ft above bottom of ravine, course E,
 Thence along ground sloping 76°, and gravelly
 79.62 Intersect N. side of sp. at the standard cor. of blocs
 32 and 33, heretofore described, which I mark C.C.
 on S. face, and raise a mound of stone 2 ft base 1 1/2
 ft high, S. of cor. Pits impracticable.
 Land mountainous and broken
 Soil stony, 4th rate,
 Timber scattering cottonwood E. of the line in bottom of canon
 Mountainous land 79.62 chs.

(29) ✓

5.02 8' N. lat. sec. 8 and 9,
 Ascend over stony ground sloping 77,
 4.60 Top of spur about 150 ft above base cor. Quarry E. Desert
 9.00 Bottom of ravine about 100 ft below top of spur, course S 40° E
 ascend
 13.60 Top of ridge 10 ft above bottom of ravine bears S 40° E, descent
 22.00 Bottom of ravine 200 ft below ridge course S 30° E
 Thence over ground sloping E,
 30.00 Top of spur, sloping E, begin steep descent over
 stony ground sloping S.E.
 35.00 Begin very abrupt descent
 40.00 Bottom of descent, east mouth of large ravine,
 Set bed sand stone 16 x 11 x 6 ins 11 ins in the ground for
 1/4 sec. cor. marked 10m N. face, and raised a mound
 of stone 2 ft base 1 1/2 ft high N. of cor. Pits impracticable
 40.90 Bottom of wash, to 2 ft deep 30 yds wide course
 E descend over ground sloping E.
 54.40 Bottom of wash 10 ft deep 40 yds wide, course E,
 59.30 three fine brass 1/2" E. S 12° W., from N. side of face,
 Mined 20 year land claim, to be abandoned,
 therefore, I
 Set quartzite boulders stone 12 x 8 x 7 ins 8 ins in the
 ground for 1/2 mander cor. of trail, sec. 8 and 9, marked
 M.C. on S. face, with 4 rods on E. face, and raised
 a mound of stone 2 ft base, 1 1/2 ft high N. of cor,
 Pits impracticable.
 67.72 Foot of descent, in last creek bottom Irrigation ditch
 19 ft deep 2 ft wide, course S 40° W, Enter alfalfa field
 Thence over level sandy loam,
 76.42 Intersect E & W. line. 6.73 chs N. of the Cong. line,
 8-9-16-17, which is a atony family
 set, marked and distance as described by the surveyor
 general, at
 80.00 Set quartzite boulders stone 15 x 8 x 6 ins 10 ins in the ground
 for SE. cor. of sec. 8, marked with 4 notches on S. and
 2 notches on N. edges, dug a pit 36 x 36 x 1 1/2 ins. in
 the sec. 8 N. dist, and raised a mound of earth
 4 ft base, 2 ft high N. W. of cor,
 this cor. is in alfalfa field,

Land mountainous and level,
 Soil, rocky, and sandy loam, 3rd & 4th rate,
 No timber,
 Mountainous 67.72 chs.

(30) ✓