

Land mountainous and level,
Soil rocky and lean - 3rd & 4th rate,
Timber; abounded in valley, Can. N. of line,
Mountainous land, 78.13 chs., 0

(31) ✓

30°-07' N, Sub sec 3, 17 and 18,
Descend over steep ground sloping E.
3.00 Bottom of ravine 100 ft below sec. cor. Course E, Can.
10.50 Top of spur 150 ft above ravine, course S80° E,
Descend over steep ground sloping S.
14.70 Bottom of ravine 150 ft below ridge; course S35° E,
ascend.
26.80 Top of spur 70 ft above bottom of ravine trace SE -
Descend abruptly over ground sloping S, W.
36.00 Bottom of ravine 200 ft below top of spur, course
S, 20° E, ascend along W. side of ravine
40.00 Set, quartzite boulder along 16 x 12 x 6 ins 1 1/2 ins in
the ground for 1/4 sec. cor. marked 1/4 sec. W. face
and raised a mound of stone 2 ft base 1 1/2 ft high
W. of cor. Pits impracticable. Descend
45.00 Bottom of ravine 100 ft below 1/4 sec. cor.
course S30° W, ascend
47.00 Top of spur, 1/2 way W. descend
50.75 Bottom of ravine 200 ft below 1/4 sec. cor.
course S35° E
53.00 Top of spur 50 ft above bottom of ravine course S10° E desc
56.20 Bottom of ravine 75 ft below top of spur, course
E. ascend,
59.00 Top of spur, 150 ft above bottom of ravine S20° E,
ascend
69.30 Bottom of ravine, 200 ft below spur, course S45° E,
ascend abruptly,
70.90 Top of spur ascend, 50 ft above ravine, thence
over broken ground, S along E.
76.38 Intersect E. & W. line 15.65 chs W. of the cor
of secs. 17-18-19 and 20, which is a stone
of simply set, marked and witnessed as described
by the surveyor general; at this point I
set, a quartzite boulder along 12 x 8 x 7 ins 2 ins in
the ground, for closing cor. of secs. 17 and 18, marked
C.C. on N. face, with 5 notches at E. and 1 notch on
W. edges. I also raised a mound of stone, 12 ft
base, 1 1/2 ft high N. of cor. Pits impracticable.

I re-establish the old cor. of secs. 17-18-19 and 20 in its
original position, as the cor. of secs. 19 and 20,
by raising a mound of stone, 12 ft base 1 1/2 ft high
S. of cor. Pits impracticable.

Land mountainous and broken,
Soil stony; 4th rate,
No timber.
Mountainous land 76.38 chs.

(32) ✓