

79.57

Intersect N. bdy of Sp. at the standard cor. of sec. 3, and 3<sup>rd</sup>. Turn to the right for descent which I mark C.C. on S. face for closing Cor. of sec. 3, 5 and 6, and pass a mound of stone 2 ft high 1 1/2 ft high 3' of cor. Pits impracticable.

Land mountainous and broken. Soil rocky and loam.  $\frac{1}{4}$  rate. Timber scattering aspens. Mountainous land 79.57 chs.

(35) ✓

40.00  
80.00

T. on a truss line bet. sec. 5, and 8, Set trap 1/4 sec cor. Intersect the cor. of sec. 4-5-8 and 9. Thence I run

4.50  
10.60  
27.75  
34.50  
39.00  
40.00

W. on a truss line bet. sec. 5 and 8, ascending over stony ground. Enter dead aspen brush, bears N & S. Clear aspen brush, cross N E & S. W. Top of spur, 400 ft above sec. cor. bears S 10° E. descend head by ravine course, S. E. ascend abruptly. Top of ridge 500 ft above sec. cor. bears N 4° S. Set quartile boulder along 16 x 6 x 3 up 11 ins in the ground for 1/4 sec. cor. marked 1/4 in N. face and round a mound of stone 2 ft high 1 1/2 ft high N. of cor. Pits impracticable. Descend over rocky ground.

44.75  
48.90

Bottom of ravine 150 ft below 1/4 sec. cor. course S. Ascend abruptly. Top of rocky ridge 150 ft above bottom ravine. course S. Ascend abruptly.

55.00  
56.25  
57.25  
62.50

Bottom of ravine 150 ft below top of ridge, bears S. and spur, sloping S. descend Bottom ravine 50 ft below spur. course S 40° E. ascend Top of spur, bears S 40° E. descend over ground sloping S. and broken by small ravines and spurs.

78.40  
79.50

Wagon tracks descent over rocky ground. Bottom of Holly canon 100 feet below the last 1/4 sec. cor. bears S 62 1/2° E. & N. 45° W. at mouth of ravine.

80.00

Thence over level ground. The cor. of sec. 5-6-7 and 8.

Land mountainous and broken. Soil rocky.  $\frac{1}{4}$  rate. No timber. Mountainous land 80.00 chs.

(36) ✓

1.50  
3.80  
6.65  
9.50  
14.80  
35.60

N. on a truss line bet. sec. 6 and 7. Ascend over stony ground. Top of spur 30 ft above sec. cor. descend. Top of descent in bottom of Holly Canon bears S 40° E & N 45° W. Thence over ground sloping S. Wood road bears N. W. & S. E. Creek bed (dry) course S. E. Ascend abruptly the N. side of Holly canon. Top of spur bears S 30° E. ascend over ground sloping S. E. Bottom ravine, course S. 70° E. D. begin trap descent.