

- 40.00 Set quartzite boulder stone 14 x 17 x 7 ins 9 ins in the ground for 1/4 sec. cor. marked 1/4 on N. face and raised a mound of stone 2 ft base 1 1/2 ft high N. of cor. Pile impracticable.
- 45.00 Top of ridge 140 ft above bottom of Canon course S 50° E. Descend.
- 49.25 Bottom of ravine 50 ft below top of ridge, course 315° W. of ascend.
- 51.50 Top of spur, course S. Descend.
- 54.50 Bottom of ravine 200 ft below ridge course S 40° W. Descend abruptly.
- 57.50 Top of ridge 100 ft above bottom ravine course S 10° W. Descend abruptly. over rocky ground.
- 65.00 Bottom of ravine 200 ft below top of ridge, course S 45° W. ascend.
- 72.75 Top of ridge 50 ft above bottom of ravine, course S. W. Descend.
- 74.60 Intersect N. E. dy of Sp. of 13 chs S. of the cor. of secs. 1-6-7 and 12, D which is a stone family set marked and witnessed as described by the surveyor general. At this point I
- Set quartzite boulder stone 16 x 10 x 8 ins 11 ins in the ground for closing cor. of secs. 6 and 7, marked C.C. on E. face, with 5 notches in S, and 1 notch on N. edge, and raised a mound of stone 2 ft base 1 1/2 ft high E. of cor. Pile impracticable.**
- Land mountainous and broken,  
Soil rocky, 4<sup>th</sup> rate,  
No timber,  
Mountainous land 74.60 chs.

(37) ✓

X (See page) the line bet. secs 38 &amp; 36 to be inserted here.

From the closing cor. of secs. 6 and 7,

I run

N. on a blank line, along N. E. dy of Sp.

7.13 The old cor. of secs. 1-6-7 and 12.

40.00 Set quartzite boulder stone 17 x 7 x 6 ins 11 ins in the ground for 1/4 sec. cor. marked 1/4 on N. face, and raised a mound of stone 2 ft base 1 1/2 ft high N. of cor. Pile impracticable.

47.66 The old 1/4 sec. cor. which is a stone family set marked and witnessed as described by the surveyor general.

From the closing cor. of secs. 6 and 7,

I run

S. on a blank line along the N. E. dy of the Sp.

33.53 The old 1/4 sec. cor. which is a stone family set, marked and witnessed as described by the surveyor general.

40.00 Set quartzite boulder stone 16 x 11 x 5 ins 11 ins in the ground for 1/4 sec. cor. marked 1/4 on N. face and raised a mound of stone 2 ft base 1 1/2 ft high N. of cor. Pile impracticable.