

From the closing cor. of sec. 7 and 18,
I run

5' on a blank line along the W. side of S. 16.
The old 1/4 sec. cor. which is a stone firmly set
marked and situated as described by the
Surveyor general.
Set a north side boulder stone 18 x 8 x 5 ins 12 ins in
the ground for 1/4 sec. cor. marked 1/4 on N. face
and raised a mound of stone 2 ft base 1 1/2 ft
high N. of cor. Post impracticable.

From the closing cor. of sec. 8, 17 and 18,

I run

1/4 on a blank random line bet sec. 18 and 19.
I find the old 1/4 sec. cor. N. 45° dist.
which is a quartzite boulder stone 12 x 10 x
5 ins marked 1/4 on N. face, firmly set in
mound of stone.
Interval bet N. 8 deg 40' & S. 91 deg 56' S. of the
cor. of sec. 13-14 10' dist 2 ft. which is a
red sand stone firmly set, marked and
situated as described by the Surveyor
general.
From this sec. cor.

I run on a blank

S 89° 18' E bet sec. 18 and 19.
Set boulder stone 18 x 10 x 10 ins 12 ins in the
ground for 1/4 sec. cor. marked 1/4 on N. face and
raised a mound of stone 2 ft base 1 1/2 ft high
N. of cor. Post impracticable.

The closing cor. of sec. 8, 17 and 18.

From the closing cor. of sec. 9 and 10,

I run

1/4 on a blank random line bet sec. 9 & 10
I make diligent search for the old 1/4 sec. cor.
but do not find any trace of the same within
a radius of 5 ft.
Interval of S 71° 48' line 3.14 chs S. of the old
cor. of sec. 8-9-10 and 17, heretofore described.
These I run

3.87±30' E on true blank line bet sec. 9 and 10.

Set quartzite boulder stone 16 x 6 x 6 ins 11 ins in the
ground for 1/4 sec. cor. marked 1/4 on N. face and
raised a mound of stone 2 ft base 1 1/2 ft high
N. of cor. Post impracticable.

The closing cor. of sec. 9 and 10.

Meanders of John London's Claim
John London having pursued his claim and
proofs of 20 years continuous adverse possession
of a tract of land in the S. 1/4 of sec. 9;
(hereinafter in accordance with the original
instructions) I proceed to locate and mark
the claim as follows:

From the old cor. of sec. 6 3.79, 16 and 17, heretofore described
a pine post 3 ins diam & 1 ft high, in place at
the S. W. cor. of the claim. Dug a shallow trench 8" deep S. E.
by N. 47° chs. 1 dist. which I mark 1/4 M. C.
on N. E. T. 4 N. m. S. W. R. 4 E. S. 19, on S. E. S. 9, on N. W.
faces. Dug a pit 36 x 36 x 42 ins S. W. cor. 4 ft dist and
raised a mound of earth around post.