

Meadows of John Hopkins claim

John Hopkins, having presented his claim and proofs of 20 year continuous adverse possession of two tracts of about 800 ac. 2 & 3, I proceed to meander the claims as follows,

To establish the meander courses on the N. side of Sec. 3, I commence at the closing cor. of Secs. 3 & 4, on the N. side of the R.R.

5.70 Tract 1 Along the N. side of the R.R. wire fence, bears N. 31° E. 49 3/6° W. 10 ft. E. of wagon road fork Canyon, up East Creek Canon, Enter John Hopkins old land claim. I

Set, quartzite boulder stone 14 X 8 X 6 ins 9 ins in the ground for meander cor. of tract, N 1/2 of Sec. 3, marked S.C. on N. with M.C. on E. face and 6 augers on S. face, and raised a mound of stone 2 ft base 1 1/2 ft high N. of cor. Pits impracticable.

0.16 Tract 2 Wire fence bears N. 70° W. and S 33 2/4 5° E, leaves John Hopkins claim and enters Lion Tunes land, Set, quartzite boulder stone 15 X 8 X 6 ins 10 ins in the ground for meander cor. of tract, N 1/2 of sec. 3, marked S.C. on N. with M.C. on W. face, and 6 augers on S. face, and raised a mound of stone 2 ft base, 1 1/2 ft high E. of cor. Pits impracticable.

1.40 Tract 3 Hence over Lion Tunes claim, Enter John Hopkins claim, defined by top of hill sloping W. at mouth of Cedar Canon, Set, quartzite boulder stone 16 X 10 X 8 ins 11 ins in the ground for meander cor. of tract, N 1/2 of sec. 3, marked S.C. on N. with M.C. on E. and 6 augers on S. face, and raised a mound of stone 2 ft base 1 1/2 ft high W. of cor. Pits impracticable.

3.03 Tract 4 South of irrigating ditch 6 ins deep 2 ft wide bears S E. and E. side of John Hopkins claim. Set quartzite boulder stone 24 X 8 X 4 ins 18 ins in the ground for meander cor. of tract, N 1/2 of sec. 3, marked S.C. on N. with M.C. on W. and 6 augers on S. face, and raised a mound of stone 2 ft base 1 1/2 ft high E. of cor. Pits impracticable.

From the last described meander cor.

I run with meanders in Sec. 3
over stony ground adjoining N. side of alfalfa field, at N. side of Cedar Canon and S. of wagon road leading S. E. in Canyon
86 1/4° E 16.70 chs. over stony ground N. of alfalfa field
86 1/2° E 14.00 " " " " " "
86 4° E 9.30 " " " " " "
to the meander cor. of tract, sec. 2 & 3.

Cedar Creek, a stream of pure water 1 1/2 deep 2 ft wide runs N.W. through the alfalfa field

Land sloping S. and nearly level.
Soil rocky, sand clay; 3/4 & 4/4 rate.
No timber

Hence in Sec. 2
over rocky hard land, along N. side of alfalfa field & S. of road and N. side of Cedar Canon. and S. of a wagon road.
86 4° E 19.10 chs over hard stony land S. of road and N. of alfalfa field, John Hopkins then at end of wagon road stacks bears N. 3 chs dist. and Geo. Shackeray's stacks bear E. 5 chs