

General Description

This township contains very little agricultural land, and is chiefly useful for grazing land. The agricultural land was being used for South Green bottom and in Cedar canon. Cottonwood, a very few scattering pine, and aspen are the only kinds of timber found in the township. There are two cities located within the portion of the Township surveyed under this contract, one in Sec. 5-97 4-8 and 9, and one in Sec. 3, 7, 4.

→ thus to precede the general description

Boundaries of Sp. 4. N. R. 4 E.
Latitudes, Departures, and closing errors,

Line designated	True bearing	Distance	Latitudes		Departures	
			N	S	E	W
1st Stand. P.M. N. or, N. body, T. 4 N. R. 4 E.	West	461.35				461.35
2nd Stand. P.M. N. or trail W. body, T. 5 N. R. 4 E.	North	10.29	10.29			
3rd Stand. P.M. N. or trail N. body, T. 4 N. R. 4 E.	West	13.44				13.44
4th Stand. P.M. N. or trail W. body, T. 4 N. R. 4 E.	50° 06' W	484.23		484.23		.85
5th Stand. P.M. N. or trail S. body, T. 4 N. R. 4 E.	89° 17' E	474.83		5.95	474.83	
6th Stand. P.M. N. or trail N. body, T. 4 N. R. 4 E.	N 70° 11' E	479.62	479.62		1.53	
Totals.			489.91	490.18	476.36	476.27
Error in latitude,				.27	8.99	.09

This sec line to be inserted after the (37) mile on page.

Preliminary to running the line bet. Secs 30 and 31. I go to the cor. of Secs. 31 and 32, on the S. body of the Sp. which is a quartzite boulder stone 8 x 8 x 5 ins above ground firmly set, marked with 5 notches on E. and 1 notch on W. edge and on the evening of Sept 15th 1895, at 7^h 44^m P.M. L.M.T. or at 8^h 10^m P.M. M.T. I observed Polaris at eastern elongation in accordance with Manual of Instructions and mark a point in the line thus determined, by a tack driven in a wooden plug set in the ground 5th sec N. of my station.

Sept 15 - 1895