

July-25-1896.

Page 188-

A 205, Surveyor General's Office  
Salt Lake City

S. Poly. T. 6. N. R. 1. W.

Survey commenced June 16-1884,  
From cor. to Secs 33-34, on S. E. dy,  
T. 6. - re-estab by me, which is a  
lime 19x10x8. 14" in the ground  
marked 3 notches E & 3 notches W, edges  
with stone mound alongside, from  
which I run E. on a true line  
bet Secs 3 & 34. Var. 16° E.

10.66 Road bears N.W. & S.E.

11.80 Wash drains N.W.

14.00 small hollow drains N.W.

40.00 no trace of old cor. set lime stone  
10x10x7 ins 7 ins in the ground for  
1/4 sec. cor. marked 1/4 on N. face -  
stone mound alongside

48. fence bears N.E. & S.W.

51.36 ditch runs N.W.

55.15 Hollow drains N.W.

(11)

(11)

50. no trace of old cor. set limestone  
20x10x5. 14" in ground for cor. to  
Secs 2-3-34 & 35, marked 2 notches  
E & 4 notches W. raised a stone  
mound alongside

Land Prush

soil 1<sup>st</sup> rate

no timber

Dense undergrowth 80. chs.

E. on true line bet Secs 2-35,

Var 16° E.

32.00 Gulch drains S.W.

40.00 set a quartzite 10x9x7 6" in ground  
for 1/4 cor. marked 1/4 on N. face. raised  
a mound of stone alongside.

57.00 a gulch drains S.W.

80.00 set a lime stone 22x10x10 16" in ground  
for cor. 1-2-35 & 36, marked  
1 notch E & 5 on W. edges. stone  
mound alongside. Land Prush  
soil 3<sup>rd</sup> rate, timber scrub pine