

Salt Lake Meridian

80. chs set a quartzite 25 x 10 x 10
 18" in ground for cor. to Secs. 19-24
 25-30. Marked S.L.M., & 2 notches
 S & 4 notches N, & raised mid stone
 along side

N. bet. Secs 19 & 24. Ya. 16° E.

- 7.50 Enter Cold Water Can, drains N.W.
 8.70 Spring Branch 10 lbs wide 7" deep, drains N.W.
 11.50 Road bears N.W. & S.E.
 15.00 Ascend.
 40.00 on top of ridge N.E. & W. Set limestone
 14 x 10 x 7, 9" in ground for 1/4 sec. cor.
 marked 1/4 S.L.M. on N. face & raised
 mid of stone along side. Ascend
 55.59 Post 4. Lot 38. "Little Harry" claim
 bears N 54° 15' E, 73 lbs dist.
 58.01 same post bears S 22° E 700 chs
 02 lbs dist.
 62.00 mouth of gulch heads S.E. house
 bears 5 chs W.

(13)

Salt Lake Meridian

(13)

- 67.39 E. side of road in Ogden Canon. bears
 N.E. & S.W., where I mark a boulder
 2 x 10 x 1 ft above ground for witness cor.
 to Secs 13-18-24, 19, with 3 notches N.
 3 notches S. edges W.C. & S.L.M.
 Building of Elect. Light Co. bears N. 6.00 chs
 68.39 S. side of Ogden Riv. 8 ft deep 125 lbs stone
 S.W. Impossible to chain farther I
 triangulate to flag on line & find same
 to be 23.00 chs dist. & set witness
 cor.

Subdivisions. Tps. 5, N. R. 1, W.

N. bet. Secs 13 & 14. Ya. 17° 15' E.

Along ridge.

- 70.50 Top of ridge bears N.W.
 32.00 Gulch drains S.E.
 40.00 Top of ridge S 84° W. Set a granite 15 x 12 x 10
 10 ins in ground for 1/4 sec. cor. marked 1/4 on
 N. side & raised mid stone along side
 70. Gulch drains S.W.