

Subdivisions - Sp. 5 N-R. 1, W.

- 80.00 Set granite 18x12x9 6" in ground
for cor. to Sec^s 11-12-13-14, marked
1 notch on E. + 4 notches on S. Edges
& raised a mound of stone along side.
E.
E. on a random line bet 12 & 13, Va 17°-15' E
40. Set temp 1/4 cor.
- 80.32 Intersect E. Edge Twp. 10 lks S. of cor.
of sec^s 12 & 13, set by mrs under
this contract.
Thence I run,
S 89°-56' W, on town line bet Sec^s
12 & 13, same Va,
- 10.00 ridge N & S,
- 20.00 Gulch drains S.W.
- 27.60 Ridge N.E. & S.W.
- 40.15 Set granite 10x10x10, 5" in ground
for 1/4 sec. cor, marked 1/4 on N. face
& raised a mound of stone along side
- 41.60 Gulch drains N.E.

Subdivisions Sp. 5 - N-R. 1, W (14)

- (14)
- 57.00 Top of divide N. & S.
- 76.00 Gulch drains S.W.
- 80.30 Cor. to Sec^s 11-12-13-14,
N. bet Sec^s 11-12,
Va 17°-15' E.
- 20.00 Top of ridge N.E. & S.W.
- 40.00 Set granite 17x11x7, 13" in ground for
1/4 sec. cor. marked 1/4 on W. face & raised
a mound of stone along side
- 43.50 Gulch drains S.W.
- 61.00 Ridge E & W,
20. Set granite 20x10x8 15" in ground
for cor. to sec^s 1-2-11-12, marked
5 notches S + 1 notch on E edge & raised
mound of stone along side
- E. on a random line bet. Sec^s 1 & 12,
Va 17°-15' E
- 40.00 also set temp 1/4 sec cor.
- 20.75 Intersect E. Edge Twp. 12 lks S of cor. sec^s 1-12