

Subdivisions - Sp. 5 N-R. 1. W

- S. 89° 55' W. on true line bet
 Secs. 1-12, same Va.,
 18.00 Ridge bars N W & S. E.
 40.37 in Gulch dcs, S. E. set granite
 15x10x5 10" in ground for 1/4 sec.
 cor. marked 1/4 on N. face & raised
 mound of stone alongside
 61.75 Top of divide N. & S.
 80.75 The cor. to Sec 2 1-2-11 & 12;

N. on random line bet Secs,
 1 & 2, Va. 17° 15' E

- 40.00 set temp 1/4 cor. cor.
 80.12 Intersection N. bdy of Sp. 75 lbs W.
 of cor. sec 2 1 & 2, which is a limestone
 6x10x10 above ground with stone
 mid alongside
 Thence I run
 50° 32' N, same Va on a
 true line bet Sec 2 1 & 2,

(15) Subdivisions Sp. 5 N-R. 1. W (15)

- 38.00 gulch drains S.W.
 40.12 set granite 12x12x8, 8" in ground
 for 1/4 sec. cor. marked 1/4 on N. face
 & raised mid of stone alongside
 60.00 Ridge bars N. E & S. W.
 76.00 Gulch drains N.
 80.12 Cor. sec 2 1-2-11-12,
 N. on re-survey line bet Sec 1-14 & 15
 Va. 17° 15' E.
 2.50 Top of hill bars E & W
 5.75 Road in hollow drains W. Road bars E & W.
 14.00 Top of ridge E & W.
 15.20 ditch runs W.
 22.00 hollow drains W.
 25.50 Top of spur bars N. & N.E.
 34.00 enter brush.
 40.00 found no trace of old cor. set a
 cobble stone 10x10x10, 6" in ground
 for re-established 1/4 cor. & raised
 mid stone alongside