

Subdivisions - Sp. 5-N-R.1.W.

- 47.00 Dry bed of cr. drs. W.
 57.20 ditch drs. W.
 58.00 road NE of S.W.
 63.50 same road NW of SE.
 72.70 Road NE of S.W.
 73.70 ditch drs. N.W.
 73.80 Wash drs. N.W.
 80. No trace of old cor; intersect
 granite stone 18x10x11 firmly
 set 12" in ground not marked
 I mark same & notch S & 2 on
 E. edges, for re-estab. cor. to sec's
 10-11-14-15 & raise mid line
 alongside
 E. on true re-survey line bet
 Sec's 11-14. Val. 17° 15' E
 6.00 creek 2 lles wide & 4" deep runs
 N.W. in broad hollow drains N.W.
 10.00 end of re-survey line

(16) Subdivisions Sp. 5-N-R.1.W (16)

- thence I run E. on random line bet
 sec's 11 & 14 from this point
 20.00 set trip 1/4 sec. cor.
 20.33 Intersect N & S. line 15 lles N. of cor.
 to sec's 11-12-13-14-
 Thence I run
 N. 89° 54' W. on true line bet sec's
 11-14.
 20.00 ridge & bars S.W. & N.E.
 27.00 creek 2 lles wide & 4" deep. S.W. & lles
 40.17 in Canon set granite 16x12x8.
 10 ins in ground for 1/4 sec. cor. under
 1/4 on N. face & raised red stone on side
 Canon drains S.W.
 5.00 Topy ridge bars N & S.E. descend
 to brush.
 70.00 enter brush hollow drs. N.W.
 70.33 end of new survey.