

Subdivisions - Sp. 5 - N - R. 1. W

N. on re-survey line bet

Secs 10 & 11. Va 17°-15' E

- 1.00 enter broad hollow drains N.W.
 8.00 creek 3 lks wide 4" deep. N.W.
 10.00 ascend bunch
 20.00 end of re-survey
 From a point 20 chs N. of cor. to
 Secs 10-11-14 & 15,
 I ran N. bet Secs 10-11,
 Va. 17°-15' E

- 36.00 Ridge NE & S.W.
 40. set granite 14x12x10 9" in ground
 for 1/4 sec. cor. marked 1/4 on W. face
 & raised mid stone alongside
 59.00 Creek 4 lks wide 3" deep. S.W.
 60.00 Bottom of hollow drains S.W.
 63.00 ascend bunch
 80.00 On S.N. point of ridge set
 granite 11x12x6 13" in ground
 for cor. Secs 2-3-10-11.
 marked 2 notches E & S. edge

(17) Subdivisions - Sp. 5 - N - R. 1. W (17)

& raised mid stone alongside

E. on random lines bet Secs.

2-11. Va 17°-15' E

40. set trap 1/4 sec. cor.
 80.15 Intersect N & S. line 5 lks N. of
 cor. to Secs 1-2-11-12.
 Thence S. run.
 N 89°-58' W. on true line bet Secs 2-11
 21.00 Bottom of Gulch drs. S.W.
 37.00 ridge across N & S.
 40.08 set granite 17x11x8 12" in ground
 for 1/4 sec. cor. marked 1/4 on N. face
 & raised mid stone alongside
 55.00 Creek 3 lks wide 4" deep runs S.
 Cañon drains S.
 80.15 Cor. Secs 2-3-10-11.