

Subdivision Sp. 5 - N - R. 1, W

N. on random line but sec 5

2-3 Var 17-15° E

40. set trap 1/4 sec. cor,  
79.80 Intersect N. bdy Sp. 60 lks  
N. of cor. of Secs 2-3, which  
is a line stone 6x10x5  
in above ground marked with  
2 notches E & 4 notches W, &  
nd stone alongside

Thence I ran S 0° 26' W. on  
true line but Sec 2-3.

70.00 in Canon drains S. Westwardly  
creek 3 lks wide 3" deep. S.W.

39.80 on ridge bars N.E. set  
granite 16x9x7-10 in ground  
for 1/4 sec. cor. marked 1/4 on W.  
& nd stone alongside

50. Canon drains S.W.

75.00 Ridge bars S.W & N.E.

79.80 Cor. sec 3 2-3-10-11.

(18) Sub. Tp. 5 - N - R. 1, W

(18)

E. on true re-survey line

but sec 3-10. Var. 17-15° E.

8.25 ditch drains N.  
15.90 fence N.W & S.E. lower cult. land  
16.00 Road N.W & S.E. house bars S 100°  
a house bars N. 200 chs  
16-30 fence N & S.

19.00 ascend fence N & S.

32.00 cross fence N.E. N. B S.W & W.

40.00 found no trace of obs. set  
granite 16x12x8 10" in ground  
for 1/4 sec. cor. marked 1/4 on N. face  
nd stone alongside

45.00 fence N.E & S.W.

50. Ascend mountain. end of re-survey.

From the point 50. chs E. of the  
cor sec 3-4-9-10 as re-established by  
Mr. Deane E. on random

line but sec 3 3-10. Var 17-15°

80. intersect N & S. line at cor to sec 5

2-3-10-11-