

August 3-4-1896.

Survey made for, Cha^s Aldoes, Jos. Felt,
and Peter Geertson, in Huntsville.

I began at 1/4 Sec. Stone on line bet Sec^s 17 & 20.

T. 6. N. - R. 2 E. which is a boulder stone, firmly set,
in N. edge of cultivated land owned by Geertson.

From which Obs^d Peak bears S 63° 42' W. and
1/4 cor. bet Sec^s 20 & 29 bears S 0° 07' E &

cor. Sec^s 17-18-19 & 20, bears S 79° 53' W. 39.06 chs
Magnetic Var. 17° 23' E.

From this 1/4 cor. I ran S 0° 07' E 263. ft. Thence

I ran W 292.2 ft to the N. line of the P.C. Geertson
tract. Thence I ran S 1° 54' E. 166. ft along
N. line of Geertson tract & E. line of W^o States bet
to Geertson's S. N. cor. and set stake for corner.

From Geertson's S. N. cor. I ran N 1° 54' W. 1162.26
ft. along Geertson's N. line & States E. line
through dense willows and marshy land,
to Geertson's N. W. cor. as described by deed.

at 1147.26 ft. point 1 ft. long pole in corner of fence, which runs
N. W. on N 1° W. 1162.26 set stake for cor. in
bottom of slough or old creek bet Geertson's

- 20 -

Aug. 4-1896

(20)

From Geertson's N. W. cor. I ran N 1° 54' W 150. Ft. for offset
line to avoid brush & slough, and set a hub 4 1/2 ft. of wire fence
bet. + 150 ft. S. of Huntsville irrigating ditch

Geertson's. From this hub I ran S 85° 54' E. on
offset 150 ft. N. of Geertson's N. line and through
at 933.9 ft. I set hub. At about N 1° 54' W. from Geertson's cor.
alfalfa at 947.5 wire fence bet. Geertson &

P.C. Wanggaard bears N 4° 14' W. at 954. At
hub in wagon road. At the above hub, 933.9 ft.

I ran S 1° 54' E. 150. ft. to Geertson's cor. and
P.C. Wanggaard's S. E. cor. set a hub. from
which Spire bears N 61° 44' W. fence ^{May 8 & 10}
to W. bears S 105 ft. - fence run N. E. bears E. 195
ft. dist - Post at S. E. cor. P.C. Wanggaard bears S 66° 20' E
215 ft. dist.

In order to test the accuracy of the above
location of S. E. cor. P.C. Wanggaard. I go to
the 1/4 Sec. cor. bet. Sec^s 17-20. T. 6. N. R. 2. E. above
described and run N. 495. ft. & set hub. to avoid
brush I offset N. & measure 300. ft. thence I
run N. 150. ft. thence I run N 5° 44' W.
and from mark 418.5 ft. to the S. E. cor. of Wanggaard
as above described. Spire bears N 61° 44' W.