

See field notes
J. page 117-118
N. 9 to 11

Sept. 1-1896.

Survey made for Charles Adams; of part of the
S.E. 1/4 of Sec 13, Tp 5, N. R. 2, W.

I begin at the cor of Sec 13 & 24, on the E. E. dty
of the Township, which is a red sandstone 20x8x8
firmly set and marked 3 notches on N. & S. notches
on S. E. dty. From which Benchmark Peak
bars, $N 9^{\circ} 18' E$. Thence I ran $N 10^{\circ} E$ ft. off
thence I ran $S 89^{\circ} 31' W$, on an offset zinc parallel
to the line bet. Sec 13 & 24, ^{which was formerly determined Sec J. 117} 1000. ft. top of a steep
hill ¹²²⁰ center of right bank of central Canal
1245 ft center of Canal 20 ft wide 2 ft deep
course N.W. 1330. ft set hub on top of hill
2650. ft. set hub. Thence I ran S. $10^{\circ} E$ ft to
set hub. no trace of old 1/4 cor. I do not
re-establish this 1/4 cor. at this time, but
find this to be its proper location, after
running $S 87^{\circ} 31' W$ 2650. ft and intersecting
the cor. of Sec 13-14-23-24, which is a
red sand stone 20x6x6, set under surface
of ground witnessed & described in field

28

(28)

notes J. page 117.

From the proper location for the 1/4 Sec cor.
bet Sec 13 & 24, I ran N. 227. ft wagon
road NW & SE, 2035. ft set hub on top of hill
65 ft S. of center of Canal $49^{\circ} W E$ of stake
from which S.W. cor. Sec 6, Pitts. new town of base $N 62^{\circ} 35' E$
marked S.W. cor of 20., 2100. center of Central
Canal N.W. 20 ft wide 2120. set hub on
N. bank of Canal, 2200, bottom of hill
2640. set hub. Bent Sec 13, Bench Pt. $N 11^{\circ} 43' E$ E. side $N 32^{\circ} 27' E$ Obs Pt. $N 72^{\circ} 31' W$
2661. ft set hub, about N. line Adams.

5280. set hub from which tel pole bears
 $N 27^{\circ} 09' W$ 119.3 ft. dist a tel pole
bears $S 86^{\circ} 47' W$, 158. ft.
Benchmark $N 12^{\circ} 09' E$. Obs Pt $N 76^{\circ} 18' E$

At 2640 = Cent Sec 13, Court house $N 32^{\circ} 47' E$
center Chim. Pitts house $N 75^{\circ} 48' E$ - N. gable
C. Smith house near tubular $S 62^{\circ} 45' E$

3
0
3
9
4
7
5