

See Plat Book
page 140

Sept. 28th 1896.

Entered following description in application of
Mrs. Elizabeth Fisher to purchase school lands:

Pt. S.W. 1/4 of Sec. 36, T. 7. N - R. 2. W. - Beg. on W. line of sd
1/4 Sec. 462. Ft. N. from S.W. Cor. thereof - Running thence
N 86.5² Ft. along Sec. line to S. line of Street, - thence
S 57° 04' E. 677. Ft. along S. line of said St. thence
S 18° 53' W 355.3 Ft. - S 48° 50' E 209.5 Ft. S 57° 48' E
745.6 Ft. - S 68° 12' W. 165.3 Ft. S 81° 45' W. 204.5 Ft
N 62° 03' W. 295.7 Ft. N 40° 54' W. 254.7 Ft. N 84° 54'
W. 108.6 Ft. N 72° 33' W. 129.5 Ft. N 69° 44' W. 241.8
Ft. to Crq. 13.38 a.

same date entered following description in
Lorenzo Fisher's application for school land.

Pt. S.W. 1/4 of Sec. 36, T. 7. N - R. 2. W. Salt Lake Mer.
Beg. at point 1327.2 Ft. N. along N. line Sec. line
along S. line St.
and 677. Ft + S 57° 04' E. from S.W. Cor. of said Sec.
Running S 57° 04' E. 559.5 Ft. along S. line of St.
S 13° W. 393.2 Ft. N. 57° 48' W 400. Ft. N 48° 50' W.
209.5 Ft. N 18° 53' E. 355.3 Ft. to Beg. 4.2 a
See Survey of same on page 31. this book.

(34.)

Sept. 29 - 1896.

Copy of description 577.

of land conveyed by Miles H. Jones to
C. Ducheneau, April 4 - 1888.


Pt. Lot 9, B 66. P.C. O.C.S. - Beg. N.W. Cor. sd lot.
N 88° 58' E. 5.44 chs. along N. line sd lot.
S. 0° 58' W. 6.16 chs. to S. line of sd lot S. 66° W.
6.20 chs. along S. line of sd lot. N 0° 58' E
8.50 chs. along N. line sd lot to Crq. 4.03 a.

Recorded W-637.

Ties to County Mont N° 2, at Cent. Wash. Ave + Canon Road
N.E. 73.1 Ft to tel. pole. - S.E. 76.9 Ft to fence Cor. post.
N.E. 56.8 Base of hydrant - S.W. 52.2 Ft. to tel. pole. -
N.W. 49.8 to pole N.E. 16.5 to St. Ry. trolley pole.

Sept. 29th 1896.

Following are ties to bolt. 33 Ft. N 0° 58' E. from N.W.
Cor. Lot 9, B 66 P.C. O.C.S. in cent. of Canon Road.

N.E. 35.5 Ft. to Soft Maple tree. N.E. 45. Ft. to honey locust,
N. E 54.5 to honey locust tree - N. W. 113.3 to S.E.
Cor. O. Badger's Brick House - S.W. 122.5 to angle
in Cor. M. Farr's House. =  N. 38° 03 1/2' E to
Eyrle Plk.