

October 1st 1896

Lat Sec 216-21-

5280 no trace of old cr. ground slopes E.
about 1320 ft N. of this point narrow drain
E. about 1500 ft and joins another ravine
from S.W. Monte Cristo bears S 89° E.

Thence I ran

I ~~some~~ variation 17245° E

over ground sloping E.

600 narrow drain N 45° E begin ascent
1350 ravine drain N. ascent abruptly
1550 top of ascent thence on ground slope N.
1700 begin ascent ground slope N.W.
2350 top of ascent thence ascent gently
2640. No trace of old cr. to Sec 2 15-16-21-22
Wallace Knob bears S 85° 15' W

Thence I ran N. lat Sec 15-16

2640 find no trace of old cr. lat Sec 15,
5385, find old cr. Sec 9-10-15-16. 20 ft
E. firmly set marked &c.

36

Thence N. lat Sec 9-10

2640 find old cr. Sec 14 a sand stone marker
"4 on upper face on ground sloping E.
5280. find old cr. to Sec 3-4-9-10
a sand stone 20 x 12 x 6, in small
amount of stone S. side of narrow drain
N.E. on ground sloping N.W. 1 ch S. of bottom
of ravine

Thence N. lat Sec 3-4

2640 ft find old cr. Sec 14 a boulder 15 x 8 x 6
firmly set marked & well known about
10 ch S. of bottom of narrow drain N.E.
and on ground sloping N.E.

5280 find closing cr. to Sec 3-4, on
N. edge of T. 8. N. R. 3 E. a gray sandstone
12 x 12 x 3 heavy base & marked
c 3 corners E & S.W. on E. slope of
ridge many N.E. on ground sloping N.E.
thence I ran I along N. body
T. 8. 528. ft & find standard