

Hogstead Survey in Sec. 36.

Oct. 13-1896.

From the cor. of Secs 26-27-35-36, T.7.N-R.2.W.

From which Proclamation Peak bears  $N 40^{\circ} 45' E$

I ran  $S 0^{\circ} 09' E$ , along line bet Secs 35 & 36.

327. Ft. 4 set stake from which S.W. cor. Zittings house

bears  $N 51^{\circ} 38' E$ , about 800 ft. dist.

48. fence  $E \& W$  on N. side of St.  $\frac{19}{20}$

867 set hub, in St, 4 ft. N. of fence on S. side St.

From which Zittings house bears  $N 28^{\circ} 12' E$

Thence I ran

East

on a line parallel to center of St, or ally, 19 ft S of fence  
& 19 ft S of road

229.9 at hub, 4 ft. N of fence, from which post at  
S.W. cor of St bears  $N 66^{\circ} 40' W$  47.7 ft. dist

a post bet S.E. cor of St. bears  $N 27^{\circ} 49' E$

25. ft dist. This street or ally continues E. to the C.P.R.R. for

Thence I ran

$N 27^{\circ} 49' E$ .

along E. side of a private alley, or street  
and laid to be the boundary bet W. Burnett on W. side  
Grawlers on the E.

278. Harrisville irrigation ditch across  $N 20^{\circ} W$

285 a fence runs  $N 75^{\circ} W$ . 34 ft in length to join  
the fence on the N. side of St. a gateway in  
the fence

369 at a point 15 ft  $N 20^{\circ} W$  from here a fence runs  
 $N 20^{\circ} W$ .

400 Fence on E. side of street. course  $N 10^{\circ} E$ .

610.5 intersect line ran E. from point 327 ft S. of cor.  
Secs 26-27-35-36. and 48 ft E. of fence

on E. side of the private road. & 33 ft S  
of fence. on the E & W. on line bet. W. Burnett  
& Grawlers <sup>S.W. cor</sup> Zittings house bears  $N 1^{\circ} 20' W$

Thence I ran

West.

48. fence N.E. & S.W. on E. side of lane

197.5 fence bears  $N 40^{\circ} N$  &  $S 20^{\circ} E$ ,

250 Harrisville ditch  $N 20^{\circ} W$

516.5 intersect line bet Secs 35-36 327. ft S.  
of Sec. line.