

Monday Dec. 13 - 1897, Survey of School Sec. 36, T. 7. N. R. 2. W.

North on random through Sec. 36  
Beg. at 1/4 Sec. Cor. on S. Line of Sec.

693. ft to Jos. Chuggs N. line bears N 88° 24' W. (from W. through this Sec)  
1479. center C.P. R.R., N. 88° 24' W. (1275 ft N 88° 24' W. to Random line)  
2415. N. side of Ransson tract bears N 88° 24' W.  
2778. fence through W. Cragin claim.  
3040. Willard Cragin's fence N. 88° 24' W.  
3759. fence bet Jacob Thurman S.W. 1/4 & N.E. 1/4  
5416. Point on N. line Sec. 36. 75 ft W. of 1/4 cor.  
Makes 1/4 Sec. line run N. 0° 48' E through Sec. 36.  
N. line bears S 79° 52' E 2632.1 ft (N 88° 24' W) - See page 46 -

S. 0° 35' W on a random line  
Along the E. side of Sec. 36, T. 7. N. R. 2. W.  
Set 1/4 cor. bears 811. ft S.W. to his S.W. cor.

4452. agrees south line, & Ducheneau N. line bears  
5436. S. E. Cor. Sec. 36. - at a point 15. ft W. of S.E. cor. of said Sec.

See field book H. page 100.  
This measurement is given as 5329 in that book.  
S. line of S. E. 1/4 Sec. 36.  
bears N 79° 25' W. 2651.1 ft  
See page 46 of this book.

N. on random through 36,

252. agrees fence N. 75° E. 81 ft N. of Persons S.E. cor.  
819. Point 1/4 N. of agrees N.W. cor. and Ransson N.E. cor.  
3082. Central Pacific N 88° 24' W.  
3648. Hackstrass fence N 88° 24' W. Chuggs.  
3948. Chuggs W. line N 88° 24' W.  
4316. Returns W. line N 88° 24' W. - thence Murdoch's  
5266. W. line Center E. fence N 88° 24' W. at a point 464 ft S. of Murdoch N.W. cor.

Friday -> Dec. 17 - 1897.

Survey made for Randall School District, in N. W. 1/4 Sec. 3. T. 6. N. R. 1. W. see page 75 for description and survey.

Dec. 20 - 1897.

Copy of deed Jos. Gibson to John B. Gibson, Jan. 10 - 1899.

Beg. 16.00 chs S. 88° 24' W. 1/4 Sec. 19. T. 6. N. R. 1. W. 27.06 chs S. 88° 24' W. 27.06 chs S. 88° 24' W. to leg 21.64 ft. right of way road wide 16.00 chs along E. end.  
1327. ft run to E. bank. Bear

make deed of above excepting strips on E. end 6.95 chs wide (E & W. and 8. chs N & S. (see Book L - page 183, field notes) from John B. Gibson to James R. McFarland. as follows: Pt. N.W. 1/4 Sec. 19. T. 6. N. R. 1. W. 2. W. - 16.50 chs S. and 6.95 chs W. of N.E. Cor. 54' 1/2 sec. - N. 20.00 ch. S. 88° 24' W. N.B. ch to beg. 16.00 ch. Deed made out and sent to John B. Gibson

Description issued to M. J. Harris in accordance with the following:  
Dec. 30 and 31<sup>st</sup> 1897.  
Traverse of P. Later tract in S. E. 1/4 Sec. 31, T. 7. N. R. 1. W. first course beg. 365. ft. N 0° 52' E. and 15. ft. N 84° 05' E from S.W. cor. S. E. 1/4 Sec.

Course	Dist.	N -	S -	E -	W -	
N 0° 24' E	2374.	2373.7		16.5		along fence on E. line of Street.
S 88° 40' E	732.5		17.0	732.7		along fence.
1° 23' W	1825.		1824.4		44.0	" "
4° 30' E	850.		365.9	767.1		" "
61° 30' E	722.7	344.8		635.1		" "
24° 45' E	71.0		64.5	30.0		" "
18° 30' E	75.0		58.7	46.7		" "
32° 30' E	557.0		254.4	488.7		" "
1° 45' W	515.5		515.4			" "
15° 36' W	1912.5	13.5			6.7	" "
10° 52' E	447.0	446.6			1912.3	" "
84° 05' W	761.0			6.7		" "
		3178.6	78.3		760.0	" "
		3174.6	3178.6	2723.0	2723.0	" "
		3174.6	3178.6	2723.0	2723.0	" "
		3174.6	3178.6	2723.0	2723.0	" "

(See Plot Book page 100)  
See also page 78 of this book.