

Jun 2-1898
Taylor.

From the point 202 f. 6 ft, 70°-07' W, from
S.E. cor. of Sec. 6. which is 30 ft E. of P.G.
Taylors W. line. I ran S 11°-13' W,
on offset line 30 ft E. of fence
set hub, 30 ft E. of fence.

280.7 ft.

Thence I ran S 46°-11' W. on an offset
line 30 ft E. of fence
set hub, 30 ft E. of post. 25 ft N. of 4 mile

136.5 ft.

Thence I ran S 19°-14' W. on offset line
30 ft E. of fence.
cross to E. side of 4 mile Cr, 4 ft. with
drum S 40° W.

70 ft.

137.4

set hub, 30 ft E. of fence Cr, 4 10 ft E. of Cr.
From which Post Oak N.E. cor. of school
house lot bears S 19°-50' E, 231. ft. dist.

Thence I run S 33°-22' W,
on offset line par. 30 ft E. of fence
4 mile Creek, S.E.,
set hub. 30 ft E. of fence. 4 4 ft. W. of Creek.

15. ft

133.7

Thence S 65°-18' W.
along offset line 30 ft E. of fence,
intersect N. boundary of P.G. Taylor. 30 ft,
S 47°-10' E. from Cr, post. lat. H.G. Taylor
& P.G. Taylor. 7.5 ft N 47°-10' W. from
an Cr. lat. same parties

75.1

Thence I run S 4°-10' E. along true body
set hub. at above cor. 10 ft N. of creek.

7.5 ft

Thence I run
S 63°-57' W, = 63°-57'
along true body line lat. Harry & P.G. T.
and 4 mile creek - N 40° W, then SW.
this line then runs par. 3 ft. S. of Cr & 3 ft
N. of fence,
set hub. 4 ft S. of Cr & 9 ft E. of fence

25.0

129.5 ft

N.W. cor. Sec. 26. T. 7. N.

4

4