

June 14-1906 - Comp. for Thoms N.E. Center in S.E. 1/4 Sec. 31, T. 2, N. R. 1, W.

Traverse of Part of Peter Lutz land beg. at point 365 ft N 0°-52' E, along 1/4 Section & 15 ft. N 84°-05' E. from S.W. cor. of said 1/4 Sec. following.

Course	Dist. ft.	N-	S-	E-	W-
N 0°-24' E	2374.0	2373.7		16.8	
S 88°-40' E	732.5		17.0	732.2	
S 12°-23' W	1825.0		1824.4		44.0
S 6°-42' E	457.1		454.0	55.3	
S 84°-05' W	761.0		76.3		760.0
		2373.7	2373.7	807.0	804.0

along fence on E. side of street.
" " " " " " of tract
" " " " " " track
" " " " " " to beg.

0-605 - Copy of deed - Lumen A. Shurtliff to Swen Anderson Dec. 28-1881 -

Beg. N.E. cor. of N.E. 1/4 Sec. 7, T. 6, N. R. 1, W. - Running thence S 13 1/2° W 8.99 chs
N 58 1/2° W 2.20 chs - S 21 1/4° W. 6.90 chs - S 89 1/2° W 6.25 ch - N 12 1/4° E. 14.10 ch
S 87 1/4° E. 2.48 chs, N 17 1/2° W. 2.00 ch, E 7.88 ch - S 1.51 ch, to beg.
12.89 ac.

Traverse table of above description. beg. at N.E. cor. of section 7.

June 19, 1906
 S. Prosser & Co. Surveyors
 Time 3 hours

0-605

	Ft.	chs	N-	S-	E-	W-
S 13°-15' W	593.34	8.99		577.54		136.0
N 58°-30' W	145.20	2.20	75.86			123.8
S 21°-15' W	455.40	6.90		424.43		165.1
S 89°-30' W	412.50	6.25		3.60		412.5
N 12°-15' E	930.60	14.10	909.41		197.45	
S 87°-15' E	163.68	2.48		7.85	163.49	
N 17°-30' W	132.00	2.00	125.89			39.7
E	520.08	7.88			520.08	
S	99.66	1.51		99.66		
			1111.16	1113.08	881.02	877.10
			1.92			3.92
			1113.08			881.02

Traverse table subdividing the above into 2 portions - E. part

①

	Ft.	chs	N-	S-	E-	W-
S 13°-15' W	593.34	8.99		577.54		136.0
N 29°-34' W	778.58	11.792	677.20			384.08
E	520.08	7.88			520.08	
S	99.66	1.51		99.66		
			677.20	677.20	520.08	520.08

along fence centering of street
to beg.

Traverse table of West part of Swen Anderson track. Beg. at pt. 593.34 N 13°-15' W from N.E. cor. Sec. 7

②

	Ft.	chs	N-	S-	E-	W-
N 58°-30' W	145.2	2.20	75.86			123.8
S 21°-15' W	455.4	6.90		424.43		165.1
S 89°-30' W	412.5	6.25		3.60		412.5
N 12°-15' E	930.6	14.10	909.41		197.45	
S 87°-15' E	163.68	2.48		7.85	163.49	
N 17°-30' W	132.00	2.00	125.89			39.70
S 29°-34' E	778.58	11.792		677.20	384.08	
			1111.16	1113.08	741.02	741.10

Description of East track - Part of S.E. 1/4 Sec. 6. Beg. at N.E. cor. of N.E. 1/4 Sec. 7, T. 6, N. R. 1, W. - Beg. at N.E. cor. of Sec. 7. Run thence S 13°-15' W. 8.99 chs - N 29°-34' W. 11.792 chs in County Road. E 7.88 chs - S. 1.51 chs to beg. 3.24 ac

③ Description of West track. Pt. S.E. 1/4 Sec. 6. Pt. N.E. 1/4 Sec. 7, T. 6, N. R. 1, W. Beg. at point 8.99 chs S 13°-15' W from N.E. cor. said Sec. 7. Run thence N 58°-30' W. 2.20 chs - S 21°-15' W. 6.90 chs - S 89°-30' W. 6.25 chs - N 12°-15' E. 14.10 ch - S 87°-15' E. 2.48 ch. N 17°-30' W. 2.00 ch S 29°-34' E. 11.792 ch in Co. Road to beg. 7.93 ac.