

158

Aug. 15 - 1916 -

Survey for Alexander Pirie, in S.E. 1/4
 Sec. 10 - T. 6 - N. - R. 1 E
 a center line of a right of way
 being 20. ft. wide

Scale 500' = 1 in.

Traverse table of line beg. at S.E. Cor. of sec. 10 T. 6 - N. - R. 1 E
 Rt of way 20' wide legs at (1) ends at (10)

Course	dist	N -	S -	E	W.	Remarks
N. 89° 47' W	455.4	1.72			455.00	along S. line of Sec 10 - To Center of Light Co. Rt of W. Stake at 388.0 = ctr. O.R. Trade lines N 57° 54' E + S 57° 54' W
N 0° 13' E	518.0	518.00		1.96		along ctr. of County Road to point of leg. of 20 ft. very ascending side-hill
N 31° 13' E	156.0	133.41		80.55		
N 8° 13' E	207.5	205.37		29.65		
N 16° 47' W	37.6	36.00			10.86	
N 3° 13' E	300.0	299.52		16.83		" " " from (1) = S 15° 56' E to S.E. Cor. Sec. 10 + N 13° 22' E
N 48° 17' W	152.0	130.29			127.07	
N 70° 25' W	100.0	33.52			94.22	from (10) = N 23° 26' E to N.E. Cor. S.E. 1/4 Sec. 10
N 51° 51' W	498.0	307.63			391.13	
N 8° 51' W	228.0	225.28			35.01	
N 45° 21' W	411.2	273.27			307.26	to point S 48° 21' E at fence N 45°
N 0° 32' W	536.2	536.18			4.99	to 12' E. of fence N 45° from (10) = S 89° 08' E to N.E. Cor. S.E. 1/4 Sec. 10
		2700.19		129.29	1426.11	

