

9/30/75

SUBDIVISION 8N, R3E

SET BRASS CAP. ON 2" X 30"  
GALV. PIPE MON. 18" DEEP IN  
MOUND OF ROCK ON ROCKY SW  
SLOPE., TO SECS. 26, 27, 34 & 35

1878 OLD NOTES READ SUB. 8N R. 2W,  
CHAINS

55.00 RIDGE BEARS N.E. ENTER TIMBER

70.00 CANYON dr. SW. LEAVE "

8.00 Set sandstone 12"x10"x9", 8" deep in mound of stone  
mound of stone, Nkd / Notch. 2E. fore CORNS 26, 27, 34 & 35 IN HOLLOW

Drain SW mountainous 80.00 due

Soil 3' rates, with traces of iron,

timber 15.00 SECS. 25, 26, 35 & 36

SET ALUM LINE POST 1" X 48" WITH

3" BRASS POINT 18" DEEP IN MOUND OF  
ROCK ON SECS. 25, 26, 35 & 36 ON  
ROCKY EAST SLOPE OF RIDGE THAT BEARS  
N 29° E