

MC-52
T.7N. R.1W, R2W.
June 1'82

325

Replaced Monument Torn out, with
Weber County Brass Cap 6" out
of gd. with Rock collar around
Brass 6-2-82 (4x4" post

B. H. M. H. next
to

FOUND ORIGINAL STONE. 5/21/82 cap)

AND PLACE MONUMENT NEXT TO STONE.

STONE HAD BEEN TIPPED SIDEWAYS
OTHER THAN THAT, NOT DISTURB.

T @ top of hill on Rebar #2 B.S.

E 1/4 cor. sec. 13 F.S.

Hor & Rt. To Weber County #325

NE 1/4 cor sec 13 229° 42' 30"

VERT & 86° 26'

Hor DIST. Corrected VERT.

2463.42'

B.S. E 1/4 cor. sec. 13

F.S. B.F. County Monument on
Intersecting Fence Lines

& Rt. 223° 34' 15"

VERT & Flat

Hor. DIST. 2159.13' Corrected VERT.

Corrected Dist (Hor.)

Weber County 2678.72'

Box Elder 2373.15'