

T.7N. R.2W.
MC-52
June 1 '82

(on top)

X @ Large rock on hill overlooking
the W 1/4 cor sec. 13 &, The center
of section 13

B.S. Center E.S. W 1/4. Double

Hor. & Rt. $173^{\circ} 21' 00''$ ($346^{\circ} 41' 45''$)

VERT & To Center sec. 13.

$86^{\circ} 26' 00''$

Hor. Dist. 1085.97 corrected Vert.

VERT & To W. 1/4 cor sec 13 (B.E.G.)

$102^{\circ} 23' 30''$

Hor. Dist. 1616.80' corrected Vert.

→ Corrected Dist 2698.40

Center Sec. 13.

Monument Replace

Replace Rebar on Fence Line with
Weber County Brass Cap Monument
6" out of ground, next to large
fence post. With 4x4 white
post. 6-2-82

B. H. M. H.