

T. 7 N. R. 1 W.
MC-52
June 23' 82

5
T @ S.E. $\frac{1}{4}$ cor. sec. 18, B.S. N.E. $\frac{1}{4}$
cor. (Iron pipe) F.S. on line
E. $\frac{1}{4}$ cor. to set
Vert \angle $84^{\circ} 21' 08''$
Hor. Dist. 2647.50'

(M.P.) NOTE:

(Moved E $\frac{1}{4}$ cor. on fence
line to match old plat's
half way between distance
wise between SE corner &
NE corner of sec. 18.)

Witnesses to East $\frac{1}{4}$ corner
9.0' To fence corner
Post NORTH
71.25' East to fence post
on E.W. fence line

Monument Description ~
E. $\frac{1}{4}$ set 9.0' South of
E & W. fence in or North
South fence line from
Intersection

4 X 4 post set (old stone
found & placed next to $\frac{1}{4}$ cor.)