

MC82-42

T.T.N. R.W.,
MC-52
June 25 '82

T @ point #1 B.S. E $\frac{1}{4}$ cor sec. 18;
(5' off North, south fence) F.S. & Rt
 $89^{\circ} 08' 20''$

Hor. Dist. From E $\frac{1}{4}$ to pt. #1
96.90'

Vert & #1 To Pt. #2 (R.R.
spike) on hill.

$275^{\circ} 02' 42''$

Hor. Dist. (corr.) 2590.76'

T @ R.R. spike #2 B.S. pt. #1; F.S.
& Rt. $252^{\circ} 26' 52''$

Vert & #2 To proposed center
sec. 17;

$97^{\circ} 11' 27''$

Hor. Dist. (corr.)

345.65'

T @ #2 (R.R. spike) B.S. #1; F.S.
& Rt. $275^{\circ} 12' 35''$ To S $\frac{1}{4}$ cor 17

Vert. & To S $\frac{1}{4}$ cor. 17

$95^{\circ} 13' 45''$

Hor. Dist. (corr.)

2918.26'

E. $\frac{1}{4}$ cor. computed Dist. To
Center Sec. 17

2672.86'

S $\frac{1}{4}$ cor. To Center (Computed
Dist. 2576.64'

(NOTE: Found old property corner
on U.P & L. R/W of old Rebar
on fence post to verify).