

Survey of City Land

Start over Co Mon 2 F.D. on
Co Mon 4 then turn angle $88^{\circ}51'$ Right and
measure East 1371.48 feet along center
of Canyon Road and set hub.

With Start over hub I Rt angle South
and find fine Shikes in Row of large
trees so I measure 10.0 farther East
and set hub (1381.48 West of Co Mon 2)
from which Point I measure South 554.0
I then deflect to Right $26^{\circ}26'$ to S. N. Cor
of Duchman Tract which is marked by a
Round stake 4 inches in diameter
and distant 45.23 . Then over this
Corner I angle or deflect to Left $99^{\circ}10'$
and measure 364 feet, and set hub,
then deflect $17^{\circ}00'$ Left and measure 578.0
and set hub, then deflect $57^{\circ}30'$ Left and
measure 304.0 ft and set hub, then deflect
to Rt $5^{\circ}35'$ and measure 2042 ft to
old hub 3" diam and which is a

Corner of Miles Jones Land.

Then set over this hub and angle
to Rt from B. S. and without re-
versing $27^{\circ}50'$ to S. N. Cor Duchman
tract and measure to this corner
(Point of Beginning) 760.5 ft. Then
set over S. N. Cor Duchman tract and
with B. S. on Jones Cor and without
reversing measure angle with 1st course
on my survey = $41^{\circ}07'$ to the Right.

For Diagram see next Page,

P. M.

Sept 25th 90