

May 26<sup>th</sup> 1891. A.M.

Survey made to locate Extension of  
Capital Avenue.  
Back & West through Block No 29 Plat C between  
Harrison Avenue to Tyler Avenue midway between  
24<sup>th</sup> & 25<sup>th</sup> Streets 30' wide.

Commence at monument at center of  
Tyler Avenue. backsight to center of  
angle right 90° S. C. repeated to 25<sup>th</sup> St  
Set two hubs for intersection -

Commence at monument at center of Harrison  
ave and 24<sup>th</sup> St - backsight to center of  
section & angle right 90° S. C. repeated. and set  
on 25<sup>th</sup> St 2 hubs for intersection -

Produce a line 2' north of center line of  
25<sup>th</sup> Street East. at center of Van Buren Ave. Hub  
Station 15 South. at 25<sup>th</sup> & Harrison Set Hub at  
2' N of center of 25<sup>th</sup> St. by intersection  
at Tyler Ave. Set Hub by intersection N of  
center of 25<sup>th</sup> St.

May 27<sup>th</sup> 1891.

Recheck line 2' N of center of 25<sup>th</sup> St.  
Set Hubs by intersection at Center 25<sup>th</sup> Harrison  
& 25<sup>th</sup> & Tyler Ave.

From Hub at Intersection of Harrison and 25<sup>th</sup> St  
produce center line 25<sup>th</sup> St angle left 90°  
to monument 24<sup>th</sup> Harrison and set Hub at  
423.26' and at 423.26' - 766.52' monument  
Center 24<sup>th</sup> & Harrison Ave.

Set Hub 447/4' East from this line at 583.26'  
point & 423.26' point for Property Corner on  
East side of Harrison Avenue on the side of  
Extension of Capital Ave.

Checked through on Tyler Ave angles on 65° 24'  
25° 30' & set stakes for property corner on Extension  
of Capital Ave.

