

June 11. 1891

Standard Measure, 7  
25th St. Hall Ave to  
Lincoln Ave.

Standard 200' steel tape, 16 lbs tension  
+ 68° F.

1st Measure, Eastward on  
slope 765.07

Temp. in sun + dust, 111°

slope 00° 16'

1341

2d. Measure. - Westward on  
slope, 765.06'

Temp. in sun + dust 106°

slope 00° 16'

average Cor. Distance 765.267

Ref temp 43°

Cor 1° for 1' = .0000068

" 1° for 765' = .0059070

" 43° " 765' = 0.2940

" for slope .0087

corrected distance 765.786

1341

Cor distance 765.788