

June 12 1891

Standard measure of Base distance on Grants
avenue between monuments on east + 25th Street

Standard 200' Steel Tape 16" divisions at 68° F.

1st Measure Northwest on ground slope 764.78

Temperature damp ground 63° F.

Slope 0° 18'

Corrected distance 764.742

2nd Measure Southward on wet muddy ground in
the sun 764.78

Temperature on wet ground 70°

Slope 0° 18'

Corrected distance 764.780

1341

Corrup 5° = -0.0260

Cor Slope -0.104

Corrected Measure 764.743

Cor Slop 2° +0.0104

on slope 0.18° - 0.104

Corrected distance 764.780

2 | 1,523
760

1341