

June 29<sup>th</sup> 1891

Standard Measure of Block distance on 23<sup>rd</sup>  
Street between monuments centers on  
Moma + Quincy avenues

200' Standard Steel tape 16 lbs tension  
+ 68° F.

1<sup>st</sup> Measure Eastward on slope 770.90

Temp in Sun + West 96° 98° 96°

Slope 0°-48'

1341

2<sup>nd</sup> Measure Westward on slope 770.95

Temp 98° 96°

Slope 0°-48'

86

Correction for 79° = +0.1572

Cor for slope 0°48' = -0.075-

Corrected distance 771.077

Dist Corrected + checked - 771.030

1341

Cor for 79° + = 0.1572

Cor for slope - 0.075-

Corrected distance 771.077

Dist Corrected + checked 771.030