

June 30th 1891
M M R

Standard measure block distance between
monuments on 24th from mouse to Quincy
avenues.

200' Standard steel tape 16 lbs tension

68° F

1st measure Eastward on slope 770.92

Temperature 86° 88°

Slope 0° 47'

B 42

2nd measure Westward on slope 770.90

Temp 92° 94°

Slope 0° 47'

87

Cor for 19° temp + = 0.0996

Cor for slope 0° 47' = - 0.0724

Corrected distance 770.947

Corrected dist 770.947

B 42

Cor for 25° temp + 0.101

Cor for slope 0° 47' = - 0.0724

Corrected distance 770.958

Dist corrected + checked 770.957

Mean distance 770.958