

Jan 20th 1891

Standard measure of Block distance on 24th
Street between monuments on Madison and
Monroe Avenues.

200' Standard Steel Tape 16 lbs tension

68° F.

1st Measure Westward on Slope 771.12'

Temperature 96° 98°

Slope 0° 45'

342

2nd Measure Eastward on Slope 771.09

Temperature 96°

Slope 0° 45'

Cor for 29° temp + 0.152

Cor for 0° 45' Slope - 0.0663

Corrected distance 771.206 $\left\{ \begin{array}{l} \text{Checked} \\ + \\ \text{Correct} \end{array} \right.$

342

Cor for 28° temp + 0.146.

Cor for 0° 45' Slope 0.066.

Corrected distance 771.171 $\left\{ \begin{array}{l} \text{Corrected} \\ + \\ \text{Checked} \end{array} \right.$

Mean distance 771.188'