

June 30 1891

Standard measure block distances
between center of monuments on
Jefferson + Madison avenues on 24th St

200' Standard Steel Tape 16 lbs tension
68° F.

1st Measure Eastward on slope 760.52

Temperature 98° 100°

Slope 0° 54'

B42

2^d Measure Westward on slope 760.50

Temperature 100° 100°

Slope 0° 54'

Correction for 31° temp 0.160

Cor for 0° 54' Slope 0.093

Corrected distance 760.526

B42

Checked
+
Correct

Cor for 32° temp + 0.165

Cor 0° 54' slope 0.093

Corrected distance 760.573

Checked
+
Correct

Mean distance 760.575