

July 9th 1891

Standard measure of Block distance
on 2ndnd strip between monuments on
Jefferson and Adams State

200' Standard steel tape 16 lbs tension
652 #.

1st Measure Eastward on slope 763.74

Temperature 75°

Slope 0° 59'

B 42

2nd Measure Westward on slope 763.73

Temperature 76°

Slope 0° 59'

Correction for temperature
 $1^{\circ} - 1 \text{ ft} = .0000068$

Correction for temp +0.041

Slope - 0.112

Corrected Distance 763.668 ✓

B 42

668
652
1326
668

763.658 Corrected Dist.