

July 9th 1891

Standard measure between monuments on Adams
avenue between 24th & 25th Street

200' Standard Steel Tape. 16 lbs tension 69° 5'

First measure from 24th St. N. Southward 400.00
to a point on slope

Temp. 78°
Slope 0° 19'

2nd measure Southward from 400 point 366.53

Temp 80°
Slope 0° 23'

Total distance 766.53

B42

First measure northward to point on slope 366.53

Temp 80°
Slope 0° 23'

From point northward to street 400.00

Temp 78°
Slope 0° 19'

Total distance 766.53

12

Correction 10° temp + 0.057

766.53
766.582

Slope Cor -

0.18

Corrected dist

766.564

Checked distance + correction = 766.573 ✓

B42

Cor 12° temp 0.062

766.53
766.592

Slope -

0.18

Corrected dist

766.574

mean

766.569

Checked and correct dist. = 766.573 ✓