

July 14<sup>th</sup> 1891.

Standard measure of Wall avenue from ~~net~~  
to 25<sup>th</sup> St.

200' Steel tape Standard 68° F - 16 lbs tension

1<sup>st</sup> Measure southward from monument on 24<sup>th</sup> to  
monument 25<sup>th</sup> ft. on ground slope 761.38

Temperature 94°

Slope 0° 05'

2<sup>nd</sup> Measure northward on slope 761.39

Temperature 98

Slope 0° 05'

1342

Correct for temp + 0.134

" " slope .00083

True distance 761.514

Corrected for slope + temp +

Checked 761.514

Cor for temp .155  
761.39

True distance 761.545

1342

Mean distance 761.544

Corrected for slope + temp + checked = 761.545