

July 14th 1891

Standard measure of Lincoln Avenue
between monuments on 24th & 25th Street

200 Steel tape. Standard 16 lbs tension
68° 8.

1st Measure northward from 25th to 24 on bank slope 762.92

Temperature 108°

Slope 0° 14'

B42

2nd Measure Southward on slope 762.93

Temperature 104°

Slope 0° 14'

14

Measure	762.92
Correction for temp 40° = +	2.07
Cor for slope 14' - -	<u>763.127</u>

Corrected for Slope & Temp 763.121

B42

Measure	762.93
Cor for temp 26° = +	1.86
Cor for slope 14' - -	<u>763.116</u>

Corrected for Slope & Temp 763.110

121
232
115